ESTIMATE # EST-000010



Ahmad Panel House

Punjab Pakistan

Bill To

SA Garden Kala Shah Kaku-Pakistan. SA Garden Kala Shah Kaku-Pakistan. Kala Shah Kaku-Pakistan. 54000 Punjab

Pakistan

Subject :

Proposal of Control Panel (VRF System)

Estimate Date: 05 Nov 2022

Expiry Date: 10 Nov 2022

Reference#: Main Control Panel of

VRF System

#	Item & Description	Qty	Rate	Amount
1	Control Panel Of VRF System INCOMING MCCB Four Pole, Icu: 36 KA 200 AFP Schneider/ABB 1 No. Mag. Contactor Four Pole (100~250 Vac) @AC-3 with 1NO + 1NC Auxiliary Contacts, 110 KW 205 AFP ABB 1 No. UV/OV Relay 415 Vac Schneider/ABB 1 No. Timer with Base 8-Pin 220 Vac Nux 1 No. Volt Meter Digital Type 0-600 Vac Entes 1 No. Volt Selector Switch 7-Positions Camsco 1 No. Ampere Meter Digital Type 0-9999 Amp. Entes 1 No. Ampere Meter Digital Type 0-9999 Amp. Entes 1 No. Current Transformer 200/5 Amp. Fico 3 Nos. Indication Lights R,Y,B (LED Type) 220 Vac Schneider 3 Nos. Four Pole SPD, Type-II, Class-II 40 KA Phoenix 1 No. MCB Single Pole for Control Icu: 06 KA 6 ASP Schneider/ABB 3 Nos. OUTGOING MCCB Triple Pole, Icu: 15 KA 40 ATP Schneider/ABB 4 Nos. MCB Single Pole, Icu: 06 KA 10 ASP Schneider/ABB 12 Nos. DOL STARTER-5.5 KW (VENTILATION FANS, DEHUMIDIFIRES) QTY 3	1.00 pcs	650,000.0 0	650,000.00

Item & Description Qty Rate Amount

MCCB Triple Pole, Icu: 15 KA 20 ATP Schneider/ABB 3 Nos. Mag. Contactor Triple Pole (100~250 Vac) @AC-3 with 1NO + 1NC Auxiliary Contacts 18 ATP ABB Nos. EOCR 5-60 Amp. Schneider 3 Nos. A-0-M Selector Switch 3-Positions Camsco 3 Nos. Push Button ON/OFF 1NO + 1NC ABB 6 Nos. Indication Lights ON, OFF (LED Type) 220 Vac Fico 6 Nos. MCB Single Pole for Control Icu: 06 KA Schneider/ABB 6 ASP 3 Nos. Terminal Blocks for Control 4 mm Onka 6 Nos. Terminal Blocks for Power 6 mm Onka 9 Nos.

PANEL SPECIFICATIONS

+N: 1x(20x5) + E: 1x(20x3)

Estimated Cubical Size: (H:1400 x W:1200 x D:400) Outdoor Floor Standing Type
14-SWG/1P-44
APH
1
No.
Electrostatic Powder Coated Paint (RAL-7035),
Outdoor Type ≥ 60 Micrones APH 1 No.
Main Tinned & Sleeved Copper Busbrs: [3Ph: 1x(20x5)

50 Amp.

Sub Total 650,000.00

Total PKR650,000.00

Notes

Looking forward for your business.

Prices are Ex-works Lahore and packed. Prices are based on current exchange rate. If currency rate will increase, price changes accordingly.

Local

I ot

Inspection and verification of equipment's / items by your authorized persons will be done before shipment.

We will provide you best quality of products/services as per engineering standards under the supervision of qualified team.

Terms & Conditions

Standard force majeure clause will be applied.

50% advance payment with confirmed P.O. Remaining 50% at the time of final inspection prior to delivery.

As mutually decided after receipt of P.O with advance payment and approval of specifications/drawings whichever is later.



2